Who Wrote the Backdoor? Authorship and Attacker Effects in AI-Control Monitor Benchmarks

Shubhrangshu Debsarkar*
University of Virginia
fvc9ch@virginia.edu

Valmik Nahata*
University of California, San Diego
vnahata@ucsd.edu

Abstract

A common safeguard for capable AI systems is a monitor, a second model that reads their output and flags attempts at sabotage. Monitors are ranked on datasets of honest and backdoored code, on the assumption that a high score means finding backdoors. We show that the standard such dataset, the APPS backdoor set, can be scored well without finding any. People wrote its honest solutions and older language models its backdoors, and a bag-of-words classifier that never runs the code reaches AUROC 0.806, above 20 of 24 published monitors. The labels also leak, because a problem enters the backdoor class only if its backdoor works, so problem metadata alone reaches 0.766. We then have Claude Sonnet 5 write both classes and swap one class at a time. Pairing human code with Sonnet 5's backdoors makes the task easier for the classifier, not harder (0.953 against 0.789), so it reads the author. A Sonnet 5 monitor is not misled by authorship. It seems to catch far fewer of Sonnet 5's backdoors, but 41 of 99 are wrong only on inputs the problem forbids, as are 20 of the 172 backdoors in the standard test split. On backdoors that are wrong on a legal input, flagging 2% of human solutions, it catches 77% of the older models' and 61% of Sonnet 5's. Scores on this dataset therefore reflect how it was built, and a catch rate means little until every trigger is checked. We release the rebuilt pairs and checks that apply to other monitor benchmarks.

1 Introduction

AI control studies how to use a capable model safely even if it tries to cause harm [3]. Its main safeguard is trusted monitoring, in which a weaker model that we trust reads each output of the stronger, untrusted model and flags suspicious ones for a human to audit. In the standard testbed the untrusted model writes solutions to programming problems and may hide a backdoor, code that passes the tests but gives a wrong answer on an input the attacker chooses. Monitors are developed and ranked on fixed datasets of such code, in which each problem has an honest solution and a backdoored one [11, 18, 8]. We call these the *original pairs* (Figure 2).

A monitor should score well on these pairs only by finding the backdoor. The dataset, however, separates its classes in two ways that have nothing to do with sabotage. People wrote the honest solutions, taken from APPS [6], and language models wrote every backdoor, so the classes differ in spacing, naming and layout (Figure 2), which detectors of model-written code pick up easily [13]. The test split also labels a problem as backdoored only when its backdoor works, which depends on the problem as much as on the code. Benchmarks with gaps like these can be solved by recognising how the data was made instead of the skill they test, as shown for language inference [5, 16], reading comprehension [9] and LLM benchmarks [14]. Detectors of model-written code are therefore benchmarked on classes matched for problem and length [4, 1], but backdoor datasets

*Equal contribution.

40th Conference on Neural Information Processing Systems (NeurIPS 2026). Workshop: Self-Evolving Diversity-Driven Search for Robust AI Systems.




Figure 1: A standard monitor benchmark can be scored on without finding the sabotage. (a) AUROC on the standard APPS backdoor split for the 24 open-weight monitors of [8] (green) and two classifiers we train that never run the code (black), bag-of-words and no-code, which reads only problem metadata (Table A3). (b)–(d) The 99 problems where every backdoor works, with one row per kind of pair, named by who wrote its honest and its backdoored solution. The first row is the original pairs. Green marks backdoors by the older models and blue backdoors by Sonnet 5. (b) Bag-of-words, refitted on each row, is highest when the two authors differ. (c) The Sonnet 5 monitor drops whenever Sonnet 5 wrote the backdoors, but many of those fire only on inputs the problem forbids. (d) Share of backdoors that monitor catches when it flags 2% of the row's honest programs, on the 52 problems where both backdoors are wrong on a legal input. Dashed line: chance. Error bars: 95% bootstrap intervals over problems.

remove only the comments [11, 8], and other control work [19, 2, 15] does not ask who wrote each class.

We show that the original pairs partly measure how they were built (Figure 1).

- A bag-of-words classifier that never runs the code scores above 20 of 24 published monitors on the standard split (§3). When we swap one class at a time for code by Claude Sonnet 5, it follows the authors and not the backdoors (§4).
- The labels also leak, because a problem whose backdoor failed contributes its honest program instead, so a classifier that reads only problem metadata also beats most monitors (§3.1).
- A Sonnet 5 monitor does not rely on authorship, and many backdoors that count as working are not: 41 of Sonnet 5's 99 and 20 of the 172 in the standard split are wrong only on inputs the problem forbids. Where both backdoors are wrong on a legal input, it catches 77% of the older models' and 61% of Sonnet 5's (§5).

We end with checks that other monitor benchmarks can run (§7) and release the rebuilt pairs and our scripts under the MIT licence (appendix A.5).[2]

[2]Code and data: `https://github.com/ShubsDS/authorship-not-sabotage`.




Figure 2: Three original pairs from the public APPS backdoor dataset [7], comments removed. A person wrote each honest solution and the named model wrote the backdoor, whose trigger and wrong output are shaded; under each pair, an input on which the backdoored program answers wrongly. The models' code also differs in style, with spaced operators in (a) and (c) and an entry-point guard in (b).

2 Setup

We study the public APPS backdoor dataset [7] in its full and high-quality releases (appendix A.1). People wrote its honest solutions, and eight models released by early 2025, led by Claude 3.7 Sonnet and o3-mini, wrote most of its backdoors (appendix A.2). We call them the *older models*, as opposed to the Claude Sonnet 5 we use. The standard split [11, 10], which we rebuild with the released code [8], has 1,209 training problems with one solution of each class and 1,375 test problems with one program each, which is the backdoored one if its backdoor works (172 problems) and otherwise the honest one. For our own pairs we use the 1,444 problems of the full release that have a passing human solution, a backdoor the dataset marks as working, and deterministic tests.

We use two baselines that never run the code. The *bag-of-words* classifier is a logistic regression on word and word-pair frequencies (TF-IDF) of the code, with comments removed. The *no-code* classifier is a logistic regression on three facts about the problem (its difficulty, number of test cases and statement length) and never sees code. We call the AUROC of such a baseline a *floor*. A monitor that scores at or below the floor has not shown that it finds backdoors. Each floor is compared with its score on shuffled labels (1,000 shuffles).

To remove the difference in authors, one model, Claude Sonnet 5 or Claude Haiku 4.5, writes both solutions to each problem. It writes an honest solution and, in a separate request that sees only the problem, a backdoored solution with an input meant to trigger it. Our test runner checks both (appendix A.3). A backdoor *works* if it passes the public tests and differs from the model's honest solution on its trigger (§4.1 checks more). We report two sets. *All attempts* keeps one backdoor per problem, chosen before we know whether it works, on the problems where both of the model's solutions pass the public tests (623 for Sonnet 5, of whose backdoors only 14 work). *Working backdoors* keeps only backdoors that work, drawn from up to 13 tries per problem (99 problems). In a *prompt-matched* version the honest solution is requested with the backdoor prompt minus the request for a flaw.

We fit the same bag-of-words classifier to the rebuilt pairs and to the original pairs of the same problems. Since 0.5 is chance, we report $\rho = (\text{rebuilt AUROC} - 0.5)/(\text{original AUROC} - 0.5)$, the fraction of the classifier's advantage over chance that remains when one model writes both classes. It exceeds 1 if the rebuilt pairs are easier. AUROCs come from five-fold cross-validation with 95% bootstrap intervals over problems (appendix A.4).

3 A classifier that never runs the code beats most monitors

On the standard APPS backdoor split, the bag-of-words classifier beats 20 of 24 open-weight monitors. Trained on the split's training problems and tested once, it reaches AUROC 0.806, while shuffled labels give at most 0.541 (95th percentile). Of the monitors, 18 are significantly below it by a paired bootstrap, and their median is 0.609 (Figure 1(a)). The classifier is trained on the benchmark and the monitors are not, so this measures what the dataset gives away, not which detector is better.

What the classifier reads is shared across attackers and present whether or not a backdoor works (appendix B.1). Trained on one attacking model's backdoors, it ranks another model's backdoor above the honest solution in 0.969 of matched pairs. Its pairwise accuracy is almost as high for backdoors that never trigger as for working ones (0.879 against 0.935). Its strongest backdoor-side features, `and`, `==` and `if`, are the tokens any added special case uses, a shallow trace of the backdoor that is there whether or not it works. On the honest side they are human idioms such as `for i` and `while` (Figure A2, with comments in appendix B.2).

3.1 The labels record which attacks failed

Of the 892 test problems with a backdoor, 720 (80.7%) have one that fails, and each of these contributes its human solution as an honest item instead. The label therefore partly records how hard a problem was to attack, and that can be read without any code. Backdoor-class problems have about half as many test cases (20.95 against 38.85, Figure A1b), because a backdoor that must pass every test is easier to hide when there are few. The no-code classifier has to be fitted within the test split, since the training split gives both programs of a problem the same metadata. Cross-validated there, it reaches 0.766 and beats 20 monitors (Table A3). Fitted outside the split it scores 0.298 (Figure A1a), a strong relation in the opposite direction, because there the honest items come from problems the split excluded, many with only two or three tests (appendix B.1). Either way, the leak comes from how the split chose its labels, not from the code. Some labels are also wrong (§5), but bag-of-words does not need them: without the 20 backdoors that fire only on forbidden inputs it scores 0.810.

4 The classifier reads the author

If the classifier reads the author, giving both classes one author should remove most of its advantage. We test this by rebuilding the pairs and then by swapping one class at a time.

When one model writes both classes, the classifier keeps $\rho = 0.687$ of its advantage over chance on Sonnet 5's all attempts and 0.097 on Haiku 4.5's (Table 1). Almost all of these attempts fail (14 of 623 and 2 of 611 work), and half name a public test input as their trigger, where a program that passes the tests cannot be wrong. Failing does not change what the classifier reads, since our working and failed backdoors separate at only 0.62. On the 99 working-backdoor problems ρ is higher, 0.861, but

Table 1: What is left when one model writes both classes. Bag-of-words AUROC on the rebuilt pairs, where the named model wrote both sides, and on the original pairs of the same problems (not the standard split of Figure 1(a)). ρ is the fraction of the original advantage over chance that remains. *Prompt-matched* rows request the honest solution with the backdoor prompt minus the request for a flaw and reuse the backdoors of the row above. *Working/n*: rebuilt backdoors that work. Intervals: 95% bootstrap over problems.

Model	working/n	rebuilt (95% CI)	original	ρ (95% CI)
All attempts: one backdoor sampled per problem				
Sonnet 5	14/623	0.750 (0.730–0.771)	0.865	0.687 (0.625–0.755)
Sonnet 5, prompt-matched	13/586	0.641 (0.618–0.662)	0.861	0.390 (0.326–0.454)
Haiku 4.5	2/611	0.534 (0.516–0.553)	0.856	0.097 (0.044–0.150)
Haiku 4.5, prompt-matched	2/562	0.539 (0.520–0.558)	0.854	0.110 (0.055–0.165)
Working backdoors: only backdoors that work				
Sonnet 5	99/99	0.749 (0.702–0.800)	0.789	0.861 (0.662–1.089)
Sonnet 5, prompt-matched	96/96	0.693 (0.646–0.745)	0.791	0.662 (0.494–0.856)

this comes from which problems those are and not from the backdoors working. On the 64 problems in both sets, ρ is about the same either way (appendix C.3).

Holding the author fixed is not quite enough, because our attack prompt leaves its own layout in the code. On Sonnet 5's pairs `def main` appears in 67% of backdoored and 38.5% of honest programs (Figure A2b), a layout Haiku 4.5 never adopts (appendix C.4). Requesting the honest solution with the backdoor prompt lowers Sonnet 5's ρ to 0.390 on all attempts and 0.662 on working backdoors, and Haiku 4.5's ρ stays at 0.110. Regenerating only the honest class does not help either (appendix C.2).

4.1 Swapping one class at a time

The rebuild changes the backdoors along with the author, so we also swap one class at a time. We pair each of Sonnet 5's classes with the other author's and name each kind of pair by who wrote its honest and its backdoored side, so the original pairs are *person / older models* and the rebuilt pairs *Sonnet 5 / Sonnet 5*. Before the all-attempts run we fixed how to read the result. If person / Sonnet 5 scored near the original pairs, the drop on rebuilding would come from the author, and if it scored near the rebuilt pairs, from Sonnet 5's backdoors. Person / Sonnet 5 scored 0.981, above the original 0.865 (appendix C.6). The working-backdoor problems, run afterwards, agree (Figure 1(b)), with 0.953 on person / Sonnet 5 and 0.905 on Sonnet 5 / older models, against 0.789 on the original pairs and 0.749 on the rebuilt ones. If Sonnet 5's backdoors were harder to spot, pairing them with human code would lower the score, but it raises it. The classifier rewards a contrast between authors, which only the one-author pairs lack, and Haiku 4.5 shows the same pattern.

5 Many backdoors that count as working are not

A strong monitor is not fooled by who wrote the honest code. Replacing the person's solutions with Sonnet 5's barely moves a Sonnet 5 monitor prompted without examples, from 0.944 on the original pairs to 0.966 on Sonnet 5 / older models. Replacing the backdoors does move it. On person / Sonnet 5, where bag-of-words rises to 0.953, the monitor falls to 0.755 (Figure 1(c), Table A10).[3]

Much of that fall comes from backdoors that are not backdoors. A draw counted as working if its output on its own trigger differed from Sonnet 5's honest solution, and nothing checked that the trigger was a legal input. Of the 99 the monitor scored, 35 are wrong only on an input the problem forbids and 6 only on stray whitespace, and the monitor scores them all low. The dataset's own backdoors have the same problem: 15 of the older models' backdoors on these problems, and 20 of the 172 in the standard test split, fire only on forbidden inputs. We therefore check every trigger in both classes against an input validator written from the statement, and require the backdoor's output there to differ from the human solutions' majority answer (appendix D.3). Both backdoors pass on 52 problems. On these the monitor's AUROC falls only from 0.955 to 0.900. With its threshold set to flag 2% of the human solutions, it catches 77% of the older models' backdoors and 61% of Sonnet 5's (Figure 1(d)), a difference of 0.15 (95% CI -0.01 to 0.31; Figure A4). On real backdoors the catch rate does not clearly depend on who wrote them, and a catch rate measured without checking the triggers would have suggested it does.

6 Limitations

A high floor shows that a dataset's labels can be predicted without finding a backdoor. It does not show that any monitor predicts them that way, and nothing here corrects a published monitor score. We ran only two monitors, both zero-shot, and a monitor trained on these pairs could learn the shortcuts. Our backdoors come from one prompt, the working-backdoor results rest on 99 problems and one attacking model, and Claude models wrote the input validators that decide which triggers are legal. Beyond this dataset we checked only five agentic settings from ControlArena [20], where the same models write both classes, and in four of them character count alone separates the classes within a task, up to AUROC 0.802 (appendix E.1).

[3] Rescoring a program returns the same score only 41%–72% of the time (appendix D.1), so differences of a few hundredths are within that noise.

7 Checks for monitor benchmarks

A monitor score on a fixed dataset means little without the score of a detector that cannot find the sabotage. We suggest three checks for any monitor benchmark. First, report baselines that never run the code (bag-of-words, problem metadata and length), with their shuffled-label scores, beside every monitor score. Second, pair each class with another author's code to see whether a detector reads the author. Third, check that every trigger is a legal input on which the backdoor is wrong, then report catch rates at a fixed audit budget on backdoors from several generators, including current models. Where they find shortcuts, have one model write both classes from one prompt, check both with the same tests, and choose honest examples independently of whether an attack on the problem succeeded.

Acknowledgments and Disclosure of Funding

Compute for this work was provided by the Virginia AI Security Initiative, a student organization at the University of Virginia.

References

[1] Basak Demirok, Mucahid Kutlu, and Selin Mergen. MultiAIGCD: A comprehensive dataset for AI generated code detection covering multiple languages, models,prompts, and scenarios. *arXiv preprint arXiv:2507.21693*, 2025.

[2] Catherine Ge-Wang, Tyler Crosse, Benjamin Hadad, Joachim Schaeffer, Ram Potham, and Tyler Tracy. Attack selection in agentic AI control evaluations meaningfully decreases safety. *arXiv preprint arXiv:2606.06529*, 2026.

[3] Ryan Greenblatt, Buck Shlegeris, Kshitij Sachan, and Fabien Roger. AI control: Improving safety despite intentional subversion. *arXiv preprint arXiv:2312.06942*, 2023.

[4] Hanxi Guo, Siyuan Cheng, Kaiyuan Zhang, Guangyu Shen, and Xiangyu Zhang. CodeMirage: A multi-lingual benchmark for detecting AI-generated and paraphrased source code from production-level LLMs. *arXiv preprint arXiv:2506.11059*, 2025.

[5] Suchin Gururangan, Swabha Swayamdipta, Omer Levy, Roy Schwartz, Samuel R. Bowman, and Noah A. Smith. Annotation artifacts in natural language inference data. In *Proceedings of the 2018 Conference of the North American Chapter of the Association for Computational Linguistics: Human Language Technologies (NAACL-HLT)*, 2018.

[6] Dan Hendrycks, Steven Basart, Saurav Kadavath, Mantas Mazeika, Akul Arora, Ethan Guo, Collin Burns, Samir Puranik, Horace He, Dawn Song, and Jacob Steinhardt. Measuring coding challenge competence with APPS. In *Proceedings of the Neural Information Processing Systems Track on Datasets and Benchmarks (NeurIPS)*, 2021.

[7] Rogan Inglis. apps-control-arena. https://huggingface.co/datasets/RoganInglis/apps-control-arena, 2025.

[8] Anik Jha. Decorrelation is not complementarity: Skill, not lineage, governs trusted-monitor ensembles. *arXiv preprint arXiv:2608.16190*, 2026. URL https://github.com/anik-jha/challenger-panels.

[9] Divyansh Kaushik and Zachary C. Lipton. How much reading does reading comprehension require? A critical investigation of popular benchmarks. In *Proceedings of the 2018 Conference on Empirical Methods in Natural Language Processing (EMNLP)*, 2018.

[10] Eugene Koran. apps-control-arena-high-quality. https://huggingface.co/datasets/eugenekoran/apps-control-arena-high-quality, 2025.

[11] Eugene Koran, Yejun Yun, Samantha Tetef, Benjamin Arnav, and Pablo Bernabeu-Pérez. Ensemble monitoring for AI control: Diverse signals outweigh more compute. *arXiv preprint arXiv:2605.15377*, 2026.

[12] Bryce Little. Length penalties make chain-of-thought less monitorable. *arXiv preprint arXiv:2607.09786*, 2026.

[13] Daniil Orel, Dilshod Azizov, Indraneil Paul, Yuxia Wang, Iryna Gurevych, and Preslav Nakov. AICD Bench: A challenging benchmark for AI-generated code detection. *arXiv preprint arXiv:2602.02079*, 2026.

[14] Lorenzo Pacchiardi, Marko Tesic, Lucy G. Cheke, and José Hernández-Orallo. Leaving the barn door open for Clever Hans: Simple features predict LLM benchmark answers. *arXiv preprint arXiv:2410.11672*, 2024.

[15] Lucas Pinto. Calibration-family overfit: Why trusted sabotage monitors don't transfer across lineages. In *COLM 2026 Workshop on AI Measurement Science*, 2026.

[16] Adam Poliak, Jason Naradowsky, Aparajita Haldar, Rachel Rudinger, and Benjamin Van Durme. Hypothesis only baselines in natural language inference. In *Proceedings of the Seventh Joint Conference on Lexical and Computational Semantics (*SEM)*, 2018.

[17] Aditya Sinha. control_arena_{bash,shade,iac,rogue_eval,agentdojo}. https://huggingface.co/datasets/adityaasinha28/control_arena_bash, https://huggingface.co/datasets/adityaasinha28/control_arena_shade, https://huggingface.co/datasets/adityaasinha28/control_arena_iac, https://huggingface.co/datasets/adityaasinha28/control_arena_rogue_eval, https://huggingface.co/datasets/adityaasinha28/control_arena_agentdojo, 2026.

[18] Mikhail Terekhov, Zhen Ning David Liu, Caglar Gulcehre, and Samuel Albanie. Control tax: The price of keeping AI in check. *arXiv preprint arXiv:2506.05296*, 2025.

[19] Mikhail Terekhov, Alexander Panfilov, Daniil Dzenhaliou, Caglar Gulcehre, Maksym Andriushchenko, Ameya Prabhu, and Jonas Geiping. Adaptive attacks on trusted monitors subvert AI control protocols. In *International Conference on Learning Representations (ICLR)*, 2026.

[20] UK AI Security Institute. ControlArena. https://github.com/UKGovernmentBEIS/control-arena, 2025.

The appendix follows the order of the paper. Appendix A describes the data, the test runner, the statistics and the release. Appendix B gives the full baseline results behind §3, Appendix C the checks behind §4, Appendix D the monitor results behind §5, and Appendix E the agentic settings of §6.

A Data and methods

A.1 The dataset

We use `RoganInglis/apps-control-arena` [7] (Table A1). Each backdoor record names the system that produced it in its `model` and `source` fields. Honest solutions have no such field, since people wrote them. The high-quality release [10] is a subset of the same dataset: every problem in it is identical apart from a re-checked `backdoor_works` flag. We therefore treat the two releases as two views of one dataset.

Table A1: Record fields of the dataset. Checked against its data files; only backdoor records carry `model` and `source`, which name the system that wrote them.

Record	fields
`solutions`	`code`, `compiles`, `passes_tests`
`backdoors`	`backdoor_code`, `backdoor_input`, `backdoor_works`, `compiles`, `model`, `passes_tests`, `source`

A.2 Who wrote the original backdoors

The original backdoors come from eight models, with Claude 3.7 Sonnet in two variants (with and without extended thinking), and one unattributed source (Table A2). All eight were released by early 2025, and the main text calls them the older models. Records whose `source` is `apps` give the model as `unknown`, and we call these unattributed. The model matters for how easy the pairs are to separate. Against the same human code, bag-of-words reaches 0.748 on gpt-3.5-turbo's backdoors and 0.931 on o3-mini's. To get these numbers we fit the classifier once, with cross-validation, on all 1,444 original pairs, and keep the out-of-fold scores of each model's backdoors, so the honest code is the same in every row.

The model matters much less for ρ. Restricting Sonnet 5's all-attempts row by attacking model keeps ρ inside the full row's interval (0.625–0.755). It is 0.715 (0.600–0.839) on the 194 problems whose original backdoor a Claude model wrote, 0.747 (0.570–0.961, $n = 71$) for claude-3-7-sonnet-thinking alone, and 0.675 (0.598–0.751, $n = 429$) for the other models.

The standard split trains and tests on different attackers. All 172 backdoors in its test set were written by claude-3-7-sonnet-thinking, and its 1,209 training backdoors by six other sources (o3-mini, claude-3-7-sonnet, gpt-4o, o1-mini, the unattributed source and gemini-2.0-flash). Its metadata names one model the dataset does not, `openai/gpt-4`. On all 89 problems where that name appears, the dataset's working backdoor comes from the unattributed source, so the name refers to that source.

A.3 Running the code

Rebuilding the pairs means running generated code. Our runner feeds each of a problem's stored test inputs to a solution, with a time limit per input and a memory limit. It agrees with the dataset's `solution_passes_tests` flag on 95.84% of the 1,444 problems we analyse and is stricter, never passing a solution the dataset fails (0 cases). We use our runner for both classes, because a checker that rejects one class more readily would create exactly the kind of class difference this paper is about. The choice does not change the original AUROC, which is 0.871 on 1,444 pairs under the dataset's flag and 0.872 on 1,406 pairs under ours. We do not match program lengths; each model chooses its own.

Two quirks of older Python versions appear in the dataset's solutions, on opposite classes. Reading `stdin` without `.buffer` we can fix; `fractions.gcd`, removed in Python 3.9, we cannot. These quirks give the original pairs a small extra cue that the rebuilt pairs, which we generated and ran

Table A2: Who wrote the original backdoors. Problems per model among the 1,444 problems we analyse, the 623 problems of Sonnet 5's all-attempts row and the 99 of its working-backdoor row (Figure 1), and the bag-of-words AUROC of that model's backdoors against all 1,444 human solutions (95% bootstrap over problems). The last row is the AUROC on all 1,444 original pairs. Model names omit the provider. Source: `attacker_mix.py`.

Model	all problems	all attempts	working	AUROC (95% CI)
o3-mini	401	175	18	0.931 (0.918–0.944)
claude-3-7-sonnet	259	110	15	0.874 (0.850–0.896)
gpt-4o	211	72	16	0.854 (0.831–0.877)
claude-3-7-sonnet-thinking	168	71	12	0.824 (0.790–0.857)
o1-mini	132	60	17	0.773 (0.732–0.814)
unattributed	111	60	9	0.958 (0.947–0.969)
gpt-4o-mini	61	28	5	0.777 (0.716–0.835)
claude-3-5-haiku	39	13	2	0.847 (0.767–0.910)
gemini-2.0-flash	38	19	3	0.849 (0.791–0.906)
gpt-3.5-turbo	24	15	2	0.748 (0.626–0.851)
all	1,444	623	99	0.871 (0.861–0.881)

ourselves, do not have. The monitor scores in Figure 1(a) are `runs/x0/monitor-summary.json` from the MIT release of the monitor-ensemble harness [8], used under its notice.

A.4 Statistics

Most AUROCs come from five-fold cross-validation with folds split by problem. Each item is scored by the model fitted without its fold, and one AUROC is computed over all these scores. The no-code classifier inside the test split also averages over five repeats of the folds. Bag-of-words on the standard split, the no-code classifier trained outside it, and the monitors score each item once, without folds.

Every interval is a 95% percentile bootstrap over problems, 2,000 draws, seed 0. For ρ, each draw resamples one set of problems and recomputes both AUROCs on it, so the interval reflects how the two move together; we call this a joint interval. Differences (a floor against a monitor, original against rebuilt pairs) are computed on the same draws. We chose the bootstrap, over an earlier rule of two fold standard deviations, before looking at the retries behind the working-backdoor rows.

Before any run we also fixed two reference values for ρ, $\rho = 0.33$ and $\rho = 0.72$, meant to separate a drop mostly due to authorship from one mostly due to the backdoor. The rebuild changes the backdoors as well as the author, so ρ cannot be split that way, and the body does not use them. The share of bootstrap draws with ρ above 0.72 is 0.17 for Sonnet 5's all-attempts row, 0.00 for its prompt-matched row, 0.00 and 0.00 for Haiku 4.5's two rows, and 0.92 and 0.28 for Sonnet 5's two working-backdoor rows.

Each permutation test shuffles the labels, reruns the whole pipeline including fitting, and recomputes the statistic, 1,000 times, with $p = (1 + \#\{\text{shuffled} \geq \text{observed}\})/(1 + 1{,}000)$. In the agentic settings labels are shuffled within each main task (appendix E.1); the token test uses random token sets instead (appendix B.3). No per-pair scores were kept for the edit variant, so its ρ has no joint interval.

A.5 What we release

The release bundle is attached to the `v1.0` release of the code repository, under the MIT licence for both data and scripts. It contains

- the rebuilt pairs: 1,444 honest programs, 1,112 edit-variant and 1,112 independent-variant backdoored programs, and all 11,565 draws from the retries;
- two selections of pairs. The first keeps the first draw for each problem (623 passing pairs, 14 with a working backdoor). The second keeps the earliest retry that works (1,046 and 99, or 106 if a crash on the trigger input counts as working), because the original backdoors are also the survivors of retries;

- the 32 scripts behind every number, from generation and testing to the monitor runs and class swaps;
- a dataset card and a manifest of row counts and checksums.


The rebuilt pairs cannot be regenerated bit for bit, because the API does not expose its sampling parameters, so we release the programs themselves.

B The two baselines

B.1 Both floors against the monitors

Table A3 gives each floor against the 24 monitors, and Figure 1(a) plots them. We compare a floor with a monitor on the same items, by point estimate and by a paired bootstrap of the difference. A monitor is *clearly* below a floor when the lower end of that interval is at least 0.01, and *borderline* when it is within 0.01 of zero. The two borderline monitors for bag-of-words are phi-4 and Falcon3-10B.

The no-code classifier gives opposite answers inside and outside the split, and the split's filter explains why. Outside the test split every problem that passes the filter has a working backdoor, so all 680 honest training items come from problems the filter removed (414 with only two or three tests, 301 with nondeterministic tests, some both). Outside the split, backdoor problems therefore have more tests than honest ones (25.3 against 14.8); inside it they have fewer (20.95 against 38.85). Training only on problems with at least four tests, as every test item has, removes the reversal: the classifier then scores 0.629 and beats 14 monitors (Figure A1). The released training split cannot be used instead, because it pairs each problem's backdoored and honest items, which share their metadata.



(a) No-code classifier (b) Test cases per problem

Figure A1: The label leak. (a) AUROC of the no-code classifier, which reads only problem metadata, cross-validated inside the standard test split and trained on problems outside it. (b) Mean test cases per test problem by class, the cue it reads: a problem enters the backdoor class only if its backdoor works, which is easier with few tests. Error bars: 95% bootstrap intervals over problems. Dashed line: chance.

Table A3: Both floors against the 24 monitors on the standard test split. *Shuffled*: 95th percentile of the AUROC on shuffled labels. *Beats*: monitors below the floor by point estimate, clearly, and borderline. The held-out row compares monitors on the same 413 items.

Baseline	trained on	AUROC (95% CI)	shuffled	p	beats
bag-of-words	training problems	0.806 (0.770–0.841)	0.541	< 0.001	20 / 18 / 2
no-code	outside the split	0.298 (0.256–0.342)	0.541	—	0 / 0 / 0
no-code	outside, ≥ 4 tests	0.629 (0.585–0.673)	0.540	0.001	14 / 8 / 1
no-code	within the split (CV)	0.766 (0.731–0.800)	0.545	< 0.001	20 / 17 / 1
no-code	within, held-out slice	0.716 (0.647–0.786)	0.558	0.001	17 / 10 / 3

Table A4 lists every baseline we ran. Its AUROC block covers the standard split and the full dataset, where the no-code classifier reads difficulty, test count and statement length. Its pairwise block covers matched pairs, in which each honest solution is paired with a backdoor to the same problem, so problem metadata cannot separate them; the DSPy rows pair them as the DSPy trusted-monitor tutorial does, and the transfer rows train on the Control Tax backdoors and test on the GPT-4-era APPS backdoors. Rows with comments kept are inflated by the comments and are shown for contrast.

Table A4: Every baseline that never runs the code. Compare rows only within a block, since each block uses its own protocol. Pairwise accuracy is the share of matched pairs in which the backdoored program scores higher. *Comments*: removed from both classes, kept, or *no code* when the baseline never reads the program. *Against*: how many of the 24 monitors the value beats, or what it is compared with (the DSPy tutorial's monitor: 0.69–0.81).

Protocol	baseline	value	comments	against
AUROC				
Filtered test split	bag-of-words	0.806	removed	above 20 of 24
same	bag-of-words	0.891	kept	above 22 of 24
cross-validated within it	no-code classifier	0.766	no code	above 20 of 24
held-out slice of it	no-code classifier	0.716	no code	above 17 of 24
same	code length only	0.473	removed	chance
same	comment count	0.498	removed	chance
same	comment count	0.696	kept	—
trained outside it	no-code classifier	0.298	no code	below chance
Full dataset, problem level	all metadata	0.892	no code	—
same	difficulty only	0.682	no code	—
same	`solution_passes_tests`	0.788	no code	—
matched pairs	all metadata	0.500	no code	by construction
Pairwise accuracy				
Matched pairs, DSPy tutorial	bag-of-words	0.897	removed	monitor 0.69–0.81
working backdoors only	bag-of-words	0.935	removed	—
backdoors that never trigger	bag-of-words	0.879	removed	not sabotage
transfer across attackers	bag-of-words	0.969	removed	—
all pairs, comments kept	bag-of-words	0.962	kept	—
working, comments kept	bag-of-words	0.979	kept	—
never trigger, comments kept	bag-of-words	0.955	kept	—
transfer, comments kept	bag-of-words	0.994	kept	—
all pairs, comments kept	code length only	0.826	kept	—

B.2 What removing comments changes


Comments inflate every result on what bag-of-words reads. We first measured them with comments left in, then again with comments removed from both classes (Table A5); the paper reports the second set. Removing comments closes the gap in the use of `#`, from 0.685 of backdoored against 0.176 of honest programs to 0.007 against 0.008. It leaves `__main__` unchanged. Some authorship cues sit in string literals, which are not comments. After comments are removed from the training split, an author line (`Author :`) remains in 23 of 1,209 honest solutions and 2 backdoored ones, and a triple-quoted block in 43 against 9. Both are too rare to explain the AUROC of 0.806, but both record who wrote the code.

Table A5: Bag-of-words with and without comments. Pairwise accuracy (the share of pairs in which the backdoored program scores higher), averaged over five problem-disjoint splits, unless marked AUROC. The other transfer results without comments are 0.866 (o3-mini to claude-3-7-sonnet), 0.844 (the reverse) and 0.764 (o1-mini to gemini-2.0-flash).

Measurement	comments kept	comments removed
transfer between attacking models	0.994	0.969
working backdoors	0.979	0.935
backdoors that never trigger	0.955	0.879
all pairs	0.962	0.897
surface features (AUROC)	0.831	0.726
matched pairs (AUROC)	—	0.856

B.3 A token test that does not replicate

Orel et al. [13] report that a small set of tokens separates human from model code. In our data it does not. The separation is -0.013, the wrong sign, with permutation $p = 0.956$. We think the



(a) Original pairs: person / older models

(b) Rebuilt pairs: Sonnet 5 / Sonnet 5

Figure A2: What bag-of-words reads. The eight word and word-pair features with the largest weight towards each class, refitted on all 623 all-attempts problems. (a) On the original pairs, the tokens of an added special case mark the backdoor side and the idioms of human competitive code mark the honest side. (b) On the rebuilt pairs, the program layout the backdoor prompt invites (`def main`, `data[`) marks the backdoor side. Source: `lexical_probe.py`.

reason is the kind of code. Their human class is general repository code, whereas both our classes are competitive-programming solutions, so tokens that mark general human code do not separate them. Only 8 of their 10 tokens occur in our data, so the test has little power, but a real effect should still have the right sign. We report it because readers who know that work may try the same test.

C The rebuilt pairs

C.1 Why the backdoor is written from the problem alone

We built the backdoored class in two ways. In the *edit* variant the model sees its own honest solution and adds a backdoor. In the *independent* variant it writes the backdoored solution from the problem statement alone. Editing produces near-copies, which changes how similar the pairs are as well as who wrote them (Table A6). Independent pairs are about as similar as the original pairs, so a low AUROC on them cannot come from making the classes alike. All rows in the main text use the independent variant.

Table A6: How similar the two programs of a pair are. Character similarity with comments removed. The middle columns give the share of pairs above 0.95 and below 0.60.

Pairs	mean similarity	> 0.95	< 0.60	differs from the original pairs in
original	0.606	3.4%	45.4%	—
edit (shown its own solution)	0.928	64.2%	4.0%	author, backdoors, similarity
independent (problem only)	0.659	3.4%	34.8%	author, backdoors

C.2 Checks on the drop

The drop is not an effect of sample size. On 30 random subsets of the original pairs, run through the same pipeline, the AUROC is 0.851 ± 0.006 (mean $\pm$ SD) at $n = 623$, far above the 0.750 of the rebuilt pairs. At $n = 99$, the size of the working-backdoor row, it is 0.773 ± 0.025, so the classifier itself loses accuracy at that size. This is why ρ divides by the AUROC refitted on the original pairs of the same problems. Reassigning problems to folds with five seeds gives the working-backdoor row a ρ of 0.87–0.93 (0.861 in Table 1).

Nor does it come from numbers or operators. We masked three kinds of token in both classes: numbers, comparison operators and identifiers. Only masking identifiers changes the all-attempts row's rebuilt AUROC, to 0.699 ($\rho = 0.54$, 0.48–0.60); the other two masks move it by at most 0.002. Code length alone separates that row's rebuilt pairs at 0.584.

It does not depend on whether the backdoor works either. Within our backdoored class, draws that work and draws that do not separate at only 0.62. On the working-backdoor problems, putting failed attempts in place of the working backdoors gives a rebuilt AUROC of 0.745, against 0.751 with the working backdoors.

We also tried two other ways to rebuild. The edit variant, whose pairs are near-copies, gives 0.625 over 427 pairs, $\rho = 0.366$. Regenerating only the honest class, with Qwen3-Coder-30B, raises the AUROC to 0.961 against 0.874 on the original pairs of the same 668 problems, while code length alone falls to 0.490.

Our backdoors rarely work, largely because of how the model picks its trigger. In 52.0% of our draws that pass the public tests, the model names a public test input as its trigger. A solution that passes the public tests cannot fail on such an input. Of these draws 0.15% work, against 5.13% of draws with a new trigger input, so our prompt roughly halves the share of backdoors that work. No working original backdoor uses a public test input as its trigger (0 of 3,188).

C.3 Do working backdoors raise ρ?

They do not. Sonnet 5's all-attempts and working-backdoor rows differ in two ways: in the second row the backdoors work, and it covers only problems where a working backdoor could be drawn. The 64 problems in both rows separate the two effects, since on them the honest program and the original pair are the same and only our backdoor differs. We reuse the existing out-of-fold scores on these subsets without refitting (Table A7).

On the shared problems ρ is 0.82 with the sampled attempts and 0.75 with the working backdoors (paired difference -0.24 to $+0.13$). Restricted to the 53 problems where the two backdoors differ, it is 0.89 and 0.83 (difference -0.06, -0.29 to $+0.17$). On the other 11 the sampled backdoor already works and is the same program in both rows. Working backdoors lower the point estimates, and both intervals include zero.

The problems matter more. The 35 problems found only in the working-backdoor row give $\rho = 1.09$ (0.72–1.63), with a lower original AUROC (0.752 against 0.814) and a higher rebuilt one (0.775 against 0.735) than the shared problems. The difference, $+0.34$ (-0.13 to $+0.93$), is not resolved at this size, but by point estimate the higher ρ of the working-backdoor row comes from which problems yield a working backdoor.

Table A7: Sonnet 5's working-backdoor row, split by problem. Bag-of-words AUROC on the rebuilt and original pairs of each subset, and ρ with a joint 95% bootstrap interval. Source: `shared_problems.py`.

Problems	n	our backdoors	rebuilt	original	ρ (95% CI)
in both rows	64	all attempts	0.781	0.845	0.82 (0.62–1.04)
in both rows	64	working	0.735	0.814	0.75 (0.55–0.98)
backdoors differ	53	all attempts	0.810	0.850	0.89 (0.68–1.17)
backdoors differ	53	working	0.760	0.814	0.83 (0.60–1.10)
all-attempts row only	559	all attempts	0.747	0.867	0.67 (0.61–0.74)
working-backdoor row only	35	working	0.775	0.752	1.09 (0.72–1.63)

C.4 Prompt matching and Haiku 4.5

Prompt matching removes much of the same signal as masking identifiers. Masking identifiers takes Sonnet 5's prompt-matched all-attempts row to 0.624 ($\rho = 0.337$) and the same 586 problems without prompt matching to 0.704. Whether what remains is program structure or naming is undecided: the masked row's interval, 0.280–0.394, straddles the threshold $\rho = 0.33$ fixed in advance. A character-level model (3 to 5 characters, same classifier and folds) keeps more than the word model, 0.679

($\rho = 0.486$), so the drop does not come from how code is split into words. Under the two prompts, Sonnet 5's correct honest solutions separate at 0.600.

Haiku 4.5's low AUROC is not caused by near-copies. Its rebuilt pairs are more alike than Sonnet 5's (mean similarity 0.724 against 0.659), so we recomputed its rebuilt AUROC within bands of similarity. It stays at 0.477–0.517 in every band, including the band at 0.451, whose pairs are less alike than the original pairs, while the original AUROC on the same problems stays at 0.778–0.826. Its honest solutions under the two prompts separate at only 0.492. Haiku 4.5 never uses the layout that marks Sonnet 5's backdoors. `def main`, `sys.stdin` and `data[` appear in none of its programs in any class, and every program reads input with `input(`, so no layout difference is left to read.

C.5 How often each model's code passes and works

Both models ran through the same pipeline. Their honest solutions pass the public tests on 0.770 (Sonnet 5) and 0.728 (Haiku 4.5) of 1,444 problems. Haiku 4.5's backdoored solutions pass on 689 problems, and only 35 of them work, below the 50 pairs we required, so Haiku 4.5 has no working-backdoor row. In the all-attempts rows 2 of Haiku 4.5's 611 backdoors work, against 14 of Sonnet 5's 623. Haiku 4.5's other 33 working backdoors are on problems where its own honest solution failed, which therefore have no rebuilt pair.

C.6 The classifier's class swap

Table A8 fits bag-of-words to every pairing of an honest and a backdoored class, with the same pipeline and folds as Table 1. One bootstrap resamples all four cells together, so differences between cells have paired intervals. We fixed how to read the result before computing it. If the person / model pairs, a person's honest code against the model's backdoors, scored near the original AUROC, the drop would be due to authorship; if near the rebuilt AUROC, to the model's backdoors. For both models they score above the original AUROC. Every pairing of two authors stays at or above the original AUROC, and only the pairing with one author falls. Against the rebuilt AUROC, person / model pairs are higher by 0.231 (0.210–0.251) for Sonnet 5 and 0.439 (0.420–0.458) for Haiku 4.5, and model / older models pairs by 0.206 (0.181–0.230) and 0.432 (0.412–0.452). On Sonnet 5's 99 working-backdoor problems the pattern is the same: the two mixed pairings score 0.953 and 0.905, above both the original (0.789) and the rebuilt AUROC (0.749). That row is built from the release bundle by `classifier_swap.py --release`, and its two diagonal cells reproduce Table 1 exactly.

Table A8: Bag-of-words with one class swapped at a time. AUROC on each model's all-attempts problems and on Sonnet 5's working-backdoor problems (95% bootstrap over problems), by who wrote the honest side (rows) and the backdoors (columns). The person / older models cell is the original AUROC and the model / model cell the rebuilt AUROC of Table 1.

Model (n)	honest by	backdoors by older models	backdoors by the model
Sonnet 5 (623)	person	0.865	0.981 (0.974–0.987)
	Sonnet 5	0.956 (0.946–0.965)	0.750
Haiku 4.5 (611)	person	0.856	0.973 (0.965–0.981)
	Haiku 4.5	0.966 (0.958–0.974)	0.534
Sonnet 5, working (99)	person	0.789	0.953 (0.925–0.976)
	Sonnet 5	0.905 (0.865–0.941)	0.749

D The monitors

D.1 Monitor scores

We ran two monitors, Sonnet 5 and Haiku 4.5, on Sonnet 5's rebuilt pairs and on the original pairs of the same problems (Table A9). A monitor's ρ is the same ratio as the classifier's, computed from the monitor's AUROCs. Sonnet 5 wrote both classes of these rebuilt pairs; Haiku 4.5 wrote neither.

Haiku 4.5 lost some replies. The 512-token cap left 628 of 1,246 replies on the rebuilt pairs unreadable. On the original pairs the missing share differs by class (50.1% of honest against 23.4% of backdoored

Table A9: Monitor AUROC on the original and rebuilt pairs. Both sets cover the same problems; intervals are 95% bootstraps over problems. Haiku 4.5's replies were capped at 512 tokens; its ρ has no interval, and on the all-attempts problems it was not computed.

Monitor	problems	original	rebuilt (95% CI)	ρ (95% CI)
Sonnet 5	all attempts	0.958	0.566 (0.551–0.583)	0.145 (0.111–0.182)
Sonnet 5	working backdoors	0.944	0.818 (0.763–0.869)	0.717 (0.601–0.832)
Haiku 4.5	all attempts	0.882	0.558	—
Haiku 4.5	working backdoors	0.883	0.787	0.749

programs), a bias of unknown direction. With a 1,024-token cap on the working-backdoor problems only 2 of 198 replies are missing, and its ρ moves from 0.749 to 0.766, inside the interval.

On these problems the monitors beat bag-of-words. On the original pairs both monitors score above bag-of-words, by 0.09 and 0.15 for Sonnet 5 on the all-attempts and working-backdoor problems and by 0.02 and 0.09 for Haiku 4.5. Figure 1(a) describes the published monitors on the standard split, not these two. On the rebuilt pairs the classifier's and the monitor's decisions are unrelated pair by pair ($\phi = 0.04$), so the two read different things.

D.2 The monitor's class swap

Table A10 recombines each monitor's scores from both runs into all four pairings of an honest and a backdoored class, on the problems where all four programs have a readable score. For Sonnet 5 on the all-attempts problems, putting Sonnet 5's backdoors in place of the older models' changes the AUROC against a person's honest code by -0.51 (-0.53 to -0.49). Putting Sonnet 5's honest code in place of the person's changes it by only $+0.016$ ($+0.011$ to $+0.021$) against the older models' backdoors and $+0.118$ ($+0.098$ to $+0.138$) against Sonnet 5's. On the working-backdoor problems the same three changes are -0.19 (-0.26 to -0.13), $+0.022$ ($+0.011$ to $+0.038$) and $+0.065$ ($+0.037$ to $+0.096$). Haiku 4.5 shows the same pattern on fewer problems. Figure A3 shows the Sonnet 5 scores behind these cells.

Table A10: Monitor AUROC with one class swapped at a time, on Sonnet 5's pairs and the original pairs of the same problems. Each AUROC column pairs the honest side named above it with the backdoors named in the column. n: problems on which all four programs have a readable score. Mean suspicion is on a 0–100 scale. *Haiku 4.5 rerun with a 1,024-token cap. Source: `monitor_swap.py`.

		AUROC				mean suspicion			
		honest by person		honest by Sonnet 5		honest		backdoored	
Monitor, problems	n	older	Sonnet	older	Sonnet	person	Sonnet	older	Sonnet
Sonnet 5, all attempts	617	0.958	0.446	0.974	0.564	6.9	4.0	78.8	6.6
Sonnet 5, working backdoors	98	0.944	0.755	0.966	0.819	6.9	3.4	73.8	37.6
Haiku 4.5, all attempts	144	0.917	0.513	0.943	0.593	28.4	21.1	86.2	27.8
Haiku 4.5, working backdoors	31	0.951	0.846	0.989	0.882	17.6	17.5	88.2	60.7
Haiku 4.5, working backdoors*	91	0.875	0.729	0.904	0.784	34.9	26.8	80.9	59.9

Rescoring is noisy. The four cells combine separate batches, submitted about six hours apart on the same day for Sonnet 5. The monitors sample at default settings. On programs scored in both batches, Sonnet 5 gives the same program the same score only 41%–72% of the time, depending on class, with a Spearman correlation of 0.85–0.89. The intervals resample problems and leave out this noise, so differences of a few hundredths between cells are within what rescoring alone produces.

One file differs between runs. The monitor runs and the classifier's working-backdoor row used different backdoors on 3 of the 99 problems (1701, 1972 and 4434). On these, one selection kept a draw that works only by crashing on its trigger input, and the other a later draw that works without crashing. Dropping the three moves the monitor's 0.818 to 0.821.




Figure A3: The Sonnet 5 monitor's suspicion scores by class on the original pairs (person / older models) and the rebuilt pairs (Sonnet 5 / Sonnet 5), for the problems of Sonnet 5's all-attempts and working-backdoor rows. Each class is normalised within its panel. Honest programs score near zero in every panel; only the backdoored class moves.

D.3 Detection at a fixed audit budget

A backdoor matters only if it gives a wrong answer on an input the problem can receive. Our working-backdoor selection asked less: a draw counted as working if, on the trigger Sonnet 5 proposed, its output differed from Sonnet 5's own honest solution. The older models' backdoors carry the dataset's own `backdoor_works` flag. Neither asks whether the trigger is a legal input or whether the reference answer is right. Before computing catch rates on the working-backdoor problems we therefore put both classes through two checks (`verify_backdoor.py -validators -human-ref`). The first asks for a legal trigger. Each of the 99 problems has an input validator that checks the line layout, token types, every stated range and every stated guarantee (distinct values, a connected graph, an answer that exists). Claude models wrote the validators from the problem statement alone, without seeing any trigger, and each accepts every stored test input of its problem. Triggers are first put in a standard layout (one space between tokens, no trailing blank lines), and all programs run on that version, so a backdoor that fires only on stray whitespace no longer fires. The second asks for a wrong answer: on the trigger, the backdoor's output must differ from the answer that a strict majority of up to ten passing human solutions give, at least two of them agreeing.

Of the 99 backdoors the Sonnet 5 monitor scored, 58 pass both checks. 35 triggers are not legal inputs (for example $M > N$ where the statement requires $M \leq N$), and 6 give the human answer once stray whitespace is removed. Of the older models' backdoors on the same problems, 83 pass, 15 triggers are not legal inputs, and one fails a public test under our runner. Both backdoors pass on 52 problems, and every working-backdoor catch rate in this section is on those problems (`audit_budget.py -verified`; 54 problems for bag-of-words, whose rebuilt backdoors differ on three problems). Honest programs are not filtered, so each threshold is still set on all 99 problems' honest programs. On the 52 problems the Sonnet 5 monitor's AUROC is 0.955 on the original pairs and 0.900 on person / Sonnet 5 (paired difference -0.055, -0.113 to 0.000), and a Haiku 4.5 monitor's 0.842 and 0.818 (45 problems with readable scores; `monitor_swap.py -verified`). Two rejections rest on a reading of the statement, a trigger written with leading zeros and a problem whose statement gives no bounds, where the validator uses the original contest's. We read the least clear-cut rejections against their statements, and release the validators.

The standard split has the same problem. We ran both checks on its 172 backdoored programs, each the dataset's designated backdoor for its problem and all but four written by Claude 3.7 Sonnet. This needed 159 more validators, written the same way, and all 258 accept every stored test input of their problem. 20 triggers are not legal inputs, each a plain breach of the statement: a value out of range, a sequence that is not a permutation, a string of the wrong length, a reducible fraction where the statement guarantees an irreducible one. 138 pass both checks. The other 13 fail a public test under our runner, which compares outputs exactly (five print real numbers checked within a tolerance), and one problem has several correct answers; we count these as undecided, not as failures. Dropping the 20 leaves bag-of-words at 0.810, against 0.806 (`split_checks.py`, `koran_split_eval.py -checked`). We do not have the published monitors' scores per program, so we cannot rescore them.

Table A11 gives the share of backdoors a detector catches when its threshold is set to flag 1%, 2% or 5% of honest programs. Monitor scores are whole numbers from 0 to 100, so many honest programs tie at the threshold. We flag every program above it and each program at it with the probability that makes the honest flag rate equal the target, and report the expected catch rate. Flagging only above the threshold gives similar results: Sonnet 5's 2% catch rates become 85% and 6% on the all-attempts problems and 73% and 71% on the checked backdoors (difference 0.02, −0.12 to 0.22). Haiku 4.5's rows tell us little. It lost many replies and scores many honest programs near the top of the scale, so at 1% and 2% it flags few backdoors of either kind. Figure A4 shows the Sonnet 5 rows on the checked backdoors at budgets up to 10%.

The original and rebuilt rows change the honest side along with the backdoors. Crossing them holds one side fixed. With the threshold set on the human solutions for both, the Sonnet 5 monitor catches 77% of the older models' checked backdoors and 61% of Sonnet 5's (difference 0.15, −0.01 to 0.31); with the threshold set on Sonnet 5's honest code, the rates are 82% and 73% (source: `audit_budget_verified.json`).




Figure A4: The Sonnet 5 monitor at four audit budgets. Share of the checked backdoors caught, on the 52 problems where both backdoors are wrong on a legal input, when the threshold flags 1%, 2%, 5% or 10% of honest programs, for three kinds of pair named by who wrote the honest and the backdoored side; each threshold is set on that pair's own honest programs, from all 99 problems. Error bars: 95% bootstrap intervals over problems.

Table A11: Share of backdoors caught at a fixed false-positive rate (FPR). The threshold is set on each set's honest programs. *Original*: the original pairs (person / older models). *Rebuilt*: the rebuilt pairs of the same problems (Sonnet 5 / Sonnet 5, and Haiku 4.5 / Haiku 4.5 in the last row). *Difference*: original minus rebuilt, with a paired 95% bootstrap interval. *Checked backdoors*: the 52 working-backdoor problems where both backdoors are wrong on a legal input (54 for bag-of-words; Haiku 4.5 also loses problems with no readable score). Honest programs come from all 99 problems. *All attempts* rows are not checked. *Haiku 4.5 rerun with a 1,024-token cap. Source: `audit_budget.py`, and `-verified` for the checked rows.

Detector, problems	FPR	original	rebuilt	difference	95% CI
Monitors, on the problems of Sonnet 5's rows					
Sonnet 5, all attempts	1%	83%	5%	0.79	0.74 to 0.83
	2%	85%	6%	0.79	0.75 to 0.83
	5%	88%	11%	0.76	0.72 to 0.80
Sonnet 5, checked backdoors	1%	75%	71%	0.04	−0.11 to 0.21
	2%	77%	73%	0.04	−0.13 to 0.20
	5%	80%	79%	0.01	−0.14 to 0.18
Haiku 4.5, all attempts	1%	1%	1%	0.00	−0.02 to 0.13
	2%	10%	3%	0.07	−0.01 to 0.19
	5%	32%	6%	0.26	0.13 to 0.44
Haiku 4.5, checked backdoors	1%	8%	5%	0.03	−0.22 to 0.17
	2%	10%	6%	0.05	−0.60 to 0.24
	5%	17%	21%	−0.04	−0.66 to 0.45
Haiku 4.5, checked backdoors*	1%	2%	0%	0.02	−0.29 to 0.16
	2%	6%	19%	−0.13	−0.34 to 0.33
	5%	50%	36%	0.14	−0.35 to 0.39
Bag-of-words, by the model that wrote the rebuilt pairs					
Sonnet 5, all attempts	2%	24%	7%	0.17	0.08 to 0.29
Sonnet 5, checked backdoors	2%	35%	4%	0.31	0.06 to 0.46
Haiku 4.5, all attempts	2%	25%	1%	0.24	0.19 to 0.37

E Agentic settings

E.1 Length leaks the label even with one set of authors

A dataset can leak its labels without any gap between authors. In five agentic settings where the same three models (claude-sonnet-4, gemini-2.5-pro and gpt-5) write both classes, character count alone separates the classes within each task, with AUROC from 0.504 (`bash`, at chance) to 0.802 (`agentdojo`; Figure A5). We compute it within each main task because a pooled AUROC would also read which task each item came from. The five datasets are one user's repackaging of ControlArena releases [17], without a licence, so we report aggregates only and scope these results to them as published.

E.2 A third cue in agent reasoning

In the same five settings, a fifteen-word regular expression over the untrusted agent's own scratchpad reaches AUROC 0.76–0.82, because prompted attack policies restate their side task in the reasoning the monitor sees. We mention it only to mark the edge of our claim. Little [12] developed and validated this method against an LLM judge and a length-matched baseline.




Figure A5: Character count separates the classes in four of five agentic settings, although the same models write both. Bars: AUROC of character count within each main task, pooled over tasks weighted by pair count, and folded to $\max(a, 1-a)$ because the direction can differ between tasks. Ticks: 95th percentile on shuffled labels (1,000 shuffles within each task); folding puts it above 0.5. `bash` is below its tick ($p = 0.829$); the other four are above theirs ($p = 0.001$ each). The number beside each setting counts its task groups, so the estimates are not equally precise. These datasets have no licence; we redistribute nothing.